

**CLARIFICATION POST PRE BID MEETING HELD ON 23 JAN 2025 WRT TENDER NOTICE FOR CONSTRUCTION OF 08 LANE 400 M ATHLETIC TRACK, CEMENTED DRAIN ON THE INNER SIDE OF THE FENCE AND 02 X CHANGING ROOMS FOR STUDENTS IN APS CHANDIMANDIR CANTT**

1. Clarification with respect to above mentioned Tender Notice are as per succeeding paras.
2. **Development of 400 mtr (8 lane) Gravel Track (Scope of Work)**
  - (i) Development of 400 mtr (8 lane) Gravel Track around the Multipurpose Sports Ground along with stations for all Track & Field Events.
  - (ii) Excavation, levelling & compaction for 400 mtr (8 lane) athletics track in the center of the ground or as directed by person in charge. Marking of inner & outer perimeter of track with burnt clay bricks flushed to the ground.
  - (iii) Laying and compaction of WBM sub base of thickness 3" after compaction.
  - (iv) Laying and compaction of coarse sand top layer of thickness 3" after compaction.
  - (v) Provision of drainage of dimensions 1.5 feet diameter & minimum 03 feet depth for draining rain water from track to outer drains on both sides to be connected with rain/storm water drain.
3. **Creation of Rain/Storm Water Drain on the Inner Side of the Fence with Slope Towards Outer Side.** Creation of covered storm water drain (RCC) along the perimeter fence of width 1' and depth as deemed necessary. Drain covers to be of cement in angle iron frame with holes on top. Slope to be in accordance with slope of ground.
4. **Masonry Work Changing room size 5 feet x 5 feet with Galvanised Sheet Roof and False Roofing (Scope of Work)**
  - (i) Provision of two PCC Plinth of Size 6 feet x 6 feet
  - (ii) Provision of 02 x Masonary Work Changing Rooms of Size 5 feet x 5 feet with false roofing.
  - (iii) Doors HPVC solid doors with handle & latching mechanism on both the sides.
  - (iv) Provision of hooks for hanging clothes and all necessary accessories.
  - (v) Grade 1 material to be used.
  - (vi) Life size mirrors in both the changing rooms.
5. **Exhaust Fan with Installation.** Exhaust Fan for 02 x changing room of branded company of dimensions of minimum 1.5 feet x 1.5 feet having air delivery of 245 CMH and speed of 2000 RPM made from ABS plastic with one year of warranty.
6. **Electrification in 02 x Changing Room.** Electrification in the 02 x changing room with light points and connection of exhaust fans.
7. Last date and time for submission of tender : - 04 Feb 2025 by 1100 hrs
8. Tender opening date and time : - 04 Feb 2025 at 1200 hrs
9. The misc details are as under: -
  - (a) All the sample of material to be approved by PMG before execution of work.
  - (b) Arch and Structural drawings dully vetted by NIT / Govt Engineering college / Govt recognized lab to be submitted by contractor before execution of work.
  - (c) Defect liability period of the work is 1 year after completion of work. Any defects occurring during the DLP will be rectified by the contractor without any cost.
  - (d) Any clause / specification mentioned anywhere in tender will be part of complete tender. In case of any discrepancies, superior specification will be followed and in case of any dispute, decision of PMG will be final and binding.